	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
78	67.32	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification and directions of the Engineer in charge.	Sqm	573.65	Rupees Five Hundred Seventy Three And Paise Sixty Five Only
79	3.00	Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, complete as per specifications and directions of the Engineer in charge.	Nos	1491.88	Rupees One Thousand Four Hundred Ninety One And Paise Eighty Eight Only
80	0.28	Providing Honne wood frames of doors, windows, clerestory windows,ventilators and other frames , wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials, labour, HOM of machineries complete as per specifications and directions of the Engineer in charge.	cum	95616.68	Rupees Ninety Five Thousand Six Hundred Sixteen And Paise Sixty Eight Only
81	11.40	Providing and fixing 65mmx90mm GRP Doorframe fabricated using E-Glass Chopped Strand Mat (CSM). U.V-stabilized Isopthalic Gelcoat and Isopthalic resin. The thickness of the GRP skin shall not be less than 2.0 mm. The doorframe consists of four segmens, which are provided with plug-in-socket arrangement in-situ in the mould. The segments are plugged in and are joined together by means of screws. The GRP frame shall be provided with wooden reinforcement of 6 locations fro high screw holding capacity for fixing metallic hold fast and shall be consolidated by filling with medium density foam/Plaster with fibre reinforcement. Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat hold fast shall be provided with the frame. complete as per specifications and directions of the Engineer in charge.	m	490.88	Rupees Four Hundred Ninety And Paise Eighty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
82	4.20	Providing and fixing factory made single leaf rigid GRP Sandwich composite door shutter of 40 mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and one layer of 450 gns E-Glass Chopped Strand Mat (CSM), impregnated with orthopthalic polyester resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 37mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not lessthan 36mmx32mmand also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc. shall be provided. A structural adhesive compatible with EPS foam shall be used for bonding the core material, the salwood reinforement and the skins. The material and process for manufacturing the door shutters shall confirm to RV-TIFAC Composites Design Centre Standards and specifications and the door shutters tested in confiramation to IS 4020-1994. The finish of shutter will be plain coulur White/IVORY/Beige/Light Grey or any other colour using high quality pigments. Excluding cost of fixtures and	m	4148.38	Rupees Four Thousand One Hundred Forty Eight And Paise Thirty Eight Only
83	9.17	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications and directions of the Engineer in charge.	Sqm	105.88	Rupees One Hundred Five And Paise Eighty Eight Only
84	3.57	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) and directions of the Engineer in charge.	Sqm	5154.19	Rupees Five Thousand One Hundred Fifty Four And Paise Nineteen Only
85	16.48	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum	Sqm	4841.38	Rupees Four Thousand Eight Hundred Forty One And Paise Thirty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	35.63	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications and directions of the Engineer in charge.	sqm	102.99	Rupees One Hundred Two And Paise Ninety Nine Only
	16.86	Qty Above 125%		102.99	Rupees One Hundred Two And Paise Ninety Nine Only
87	1521.66	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses. complete as per specifications and directions of the Engineer in charge.	Sqm	750.75	Rupees Seven Hundred Fifty And Paise Seventy Five Only
88	814.16	Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications and directions of the Engineer in charge.	Sqm	44.28	Rupees Forty Four And Paise Twenty Eight Only
89	140.69	Providing and installing of approved make pre painted Galvalume iron Accessories, like, plain, ridges, plain gutter, plain flashing, corner Trim, etc. The total coated thickness (TCT) of the sheet shall be 0.47 mm +/- 0.02 tolerance mm Zinc-Alu Alloy coating AZ 150 gsm as per ASTM 1397/755 -550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling / self tapping screws of 25 mm length. (width upto 500-600 mm only), to be fixed over the existing purlins, rafters, channels and trusses.complete as per specifications and directions of the Engineer in charge.	Sqm	719.95	Rupees Seven Hundred Nineteen And Paise Ninety Five Only
90	611.38	Supply and Installation of approved Wooden Floor for Indoor Hall - Maple Flooring with PU Scaler and coat polish 20mm,thickness*60mm width*2000mm, third &better grade treated sleepers of size 30*60mm to be installed 30cm center to center 20mmm professional EPDM rubber pad inclusive of HOM, labour etc. complete as per specifications and directions of the Engineer in charge.	Sqm	15159.38	Rupees Fifteen Thousand One Hundred Fifty Nine And Paise Thirty Eight Only
91	2.00	Providing and fixing white vitreous china clay,flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets ,32mm C.P brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications and directions of the Engineer in charge.	Unit	3436.13	Rupees Three Thousand Four Hundred Thirty Six And Paise Thirteen Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	2.50	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. complete as per specifications and directions of the Engineer in charge.	Each	163.63	Rupees One Hundred Sixty Three And Paise Sixty Three Only
	3.50	Qty Above 125%		163.63	Rupees One Hundred Sixty Three And Paise Sixty Three Only
93	50.00	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications and directions of the Engineer in charge.For Rain water pipe.do - 110 mm dia	m	473.55	Rupees Four Hundred Seventy Three And Paise Fifty Five Only
	116.40	Qty Above 125%		473.55	Rupees Four Hundred Seventy Three And Paise Fifty Five Only
94	40.98	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications and directions of the Engineer in charge.For Rain water pipe. do-160mm dia	m	930.74	Rupees Nine Hundred Thirty And Paise Seventy Four Only
95	2.50	Providing and fixing white vitreous china clay, water closet europeon type (pedestal type, p-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level,P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets , 40mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design,painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications and directions of the Engineer in charge.	Each	5409.25	Rupees Five Thousand Four Hundred Nine And Paise Twenty Five Only
	1.50	Qty Above 125%		5409.25	Rupees Five Thousand Four Hundred Nine And Paise Twenty Five Only
96	0.00	Providing and fixing white vitreous china clay,flat back or half stall urinal basin of size 580x380x350mm in the range of two with 7.5 litres P.V.C automatic flushing cistern, C.I / M.S brackets ,standard flush pipe and C.P brass spreaders with brass unions and G.I clamps, C.I trap with outlet grating and other couplings in C.P brass, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications and directions of the Engineer in charge.	Unit	8810.73	Rupees Eight Thousand Eight Hundred Ten And Paise Seventy Three Only
97	2.00	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 Litre capacity) and directions of the Engineer in charge.	Each	22356.95	Rupees Twenty Two Thousand Three Hundred Fifty Six And Paise Ninety Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	4.00	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer in charge.	Each	188.65	Rupees One Hundred Eighty Eight And Paise Sixty Five Only
99	2.50	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer in charge.	Each	154.00	Rupees One Hundred Fifty Four Only
	1.50	Qty Above 125%		154.00	Rupees One Hundred Fifty Four Only
100	2.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer in charge.	Each	366.71	Rupees Three Hundred Sixty Six And Paise Seventy One Only
101	50.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,)complete as per specifications and directions of the Engineer in charge.20mm nominal OD pipes	m	256.03	Rupees Two Hundred Fifty Six And Paise Three Only
	2.00	Qty Above 125%		256.03	Rupees Two Hundred Fifty Six And Paise Three Only
102	31.75	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,)complete as per specifications and directions of the Engineer in charge.25mm nominal OD pipes	m	319.55	Rupees Three Hundred Nineteen And Paise Fifty Five Only
103	2.00	Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications and directions of the Engineer in charge.	Unit	1239.70	Rupees One Thousand Two Hundred Thirty Nine And Paise Seventy Only
104	2.00	Providing and fixing C.P brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P brass screws including cost of materials, labour complete as per specifications and directions of the Engineer in charge.	Unit	806.58	Rupees Eight Hundred Six And Paise Fifty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	2.00	Providing wash basin brackets of approved 1st qyuality and make confirming to ISI specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot.complete as per specifications and directions of the Engineer in charge.	Pair	261.80	Rupees Two Hundred Sixty One And Paise Eighty Only
106	2.00	Constructing brick masonry inspection chamber 600x600mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 600x600mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 600x600mm. .complete as per specifications and directions of the Engineer in charge.	NO	9265.99	Rupees Nine Thousand Two Hundred Sixty Five And Paise Ninety Nine Only
107	0.00	Providing of stoneware gully trap of approved quality and make fixing in M-15 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all)..complete as per specifications and directions of the Engineer in charge.10 cms x 10 cms	Nos	206.94	Rupees Two Hundred Six And Paise Ninety Four Only
108	0.00	Open Conduit System - supplying heavy gauge PVC conduit pipe dia mm thick comfirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.)complete as per specifications and directions of the Engineer in charge. 19/20mm dia, 2mm thick	Mtr	50.05	Rupees Fifty And Paise Five Only
109	0.00	Open Conduit System - supplying heavy gauge PVC conduit pipe dia mm thick comfirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.)complete as per specifications and directions of the Engineer in charge. 25mm dia, 2mm thick	Mtr	65.45	Rupees Sixty Five And Paise Forty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
10	75.00	Open Conduit System - supplying heavy gauge PVC conduit pipe dia mm thick comfirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.)complete as per specifications and directions of the Engineer in charge. 32mm dia, 2mm thickk	Mtr	92.40	Rupees Ninety Two And Paise Forty Only
11	12.60	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. complete as per specifications and directions of the Engineer in charge. 19/20mm dia, 2mm thick	Rmt	51.01	Rupees Fifty One And Paise One Only
112	0.00	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. complete as per specifications and directions of the Engineer in charge.25mm dia, 2mm thick	Rmt	53.90	Rupees Fifty Three And Paise Ninety Only
113	0.00	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. complete as per specifications and directions of the Engineer in charge. 32mm dia, 2mm thick	Rmt	81.81	Rupees Eighty One And Paise Eighty One Only
114	15.00	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, complete for each outlet.Short point upto 3m .complete as per specifications and directions of the Engineer in charge	Point	202.13	Rupees Two Hundred Two And Paise Thirteen Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
115	12.50	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, complete for each outlet.Medium point above 3m - 6m .complete as per specifications and directions of the Engineer in charge	Point	277.20	Rupees Two Hundred Seventy Seven And Paise Twenty Only
	62.50	Qty Above 125%		277.20	Rupees Two Hundred Seventy Seven And Paise Twenty Only
116	47.25	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, abhesive paste ets, and running befour concreting and slab. The conduit should de tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire whereever necessary .25mm dia, 2mm thick. complete as per specifications and directions of the Engineer in charge.	Mtr	52.94	Rupees Fifty Two And Paise Ninety Four Only
	12.75	Qty Above 125%		52.94	Rupees Fifty Two And Paise Ninety Four Only
117	0.00	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, abhesive paste ets, and running befour concreting and slab. The conduit should de tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire whereever necessary .32mm dia, 2mm thick. complete as per specifications and directions of the Engineer in charge.	Mtr	83.74	Rupees Eighty Three And Paise Seventy Four Only
118	0.00	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary.19/20mm dia, 2mm thick. complete as per specifications and directions of the Engineer in charge.	Mtr	40.43	Rupees Forty And Paise Forty Three Only
119	15.00	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary.25mm dia, 2mm thick. complete as per specifications and directions of the Engineer in charge.	Mtr	52.94	Rupees Fifty Two And Paise Ninety Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
120	6.00	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall .1 - 3 Way.complete as per specifications and directions of the Engineer in charge.	Each	96.25	Rupees Ninety Six And Paise Twenty Five Only
121	0.00	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall .4 - 5 Way.complete as per specifications and directions of the Engineer in charge.	Each	0.00	Rupees Nil
122	6.00	Supplying 6A flush type socket and 6 amp flush type SP switch either surface/flush mountinh in existing gang box or in 4mm thik plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wire as required as per IS 1293 and IS 3654.6AMP 3/5 and Switch.complete as per specifications and directions of the Engineer in charge.	Each	132.83	Rupees One Hundred Thirty Two And Paise Eighty Three Only
123	0.00	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854.16Amps Combined switch and socket with indication.complete as per specifications and directions of the Engineer in charge.	No	195.39	Rupees One Hundred Ninety Five And Paise Thirty Nine Only
124	0.00	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854.Electronic stepped regulator..complete as per specifications and directions of the Engineer in charge.	Nos	212.71	Rupees Two Hundred Twelve And Paise Seventy One Only
125	56.63	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements.2.5sqmm. complete as per specifications and directions of the Engineer in charge.	Mtr	31.76	Rupees Thirty One And Paise Seventy Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	843.38	Qty Above 125%		31.76	Rupees Thirty One And Paise Seventy Six Only
126	256.75	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements 4sqmm. complete as per specifications and directions of the Engineer in charge.	Mtr	45.24	Rupees Forty Five And Paise Twenty Four Only
	223.25	Qty Above 125%		45.24	Rupees Forty Five And Paise Twenty Four Only
127	4.00	Supplying and fixing Metal Fan Box with Round Hook complete as per specifications and directions of the Engineer in charge.	Nos	86.63	Rupees Eighty Six And Paise Sixty Three Only
128	1.00	Supplying and fixing of regular MCB distribution boards on wall/woodboard/flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB'S single phase/ 3 phase / single door with powder coated painting made out of SWG MS enclosute.12 way SP & N.complete as per specifications and directions of the Engineer in charge.	Each	1222.38	Rupees One Thousand Two Hundred Twenty Two And Paise Thirty Eight Only
129	15.00	Supply and fixing miniature circuit breakers on the existing MCB distribution boards using necessary fixing meterials and "C" type curve, Indiator ON/OFF energy cross -3 with as required confirming to IEC 60898.6-32 AMPS DP.complete as per specifications and directions of the Engineer in charge.	Each	919.19	Rupees Nine Hundred Nineteen And Paise Nineteen Only
130	1.25	Supplying, fixing and wiring earth electrode for grounding conduits , I.C. cutouts and others equipments on the meter board using 40mm dia 2.90mm long buried in a pit.. the pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit ect, is to be established through GI wire of size as ISI specification 7.3.3 of IS 732 using 12mm dia bolt, nut, washers and check nuts ect... the pipe shall have 16 through holes of 122mm dia, ..complete as per specifications and directions of the Engineer in charge.	No	3031.88	Rupees Three Thousand Thirty One And Paise Eighty Eight Only
	2.75	Qty Above 125%		3031.88	Rupees Three Thousand Thirty One And Paise Eighty Eight
131	80.00	Supplying and running of GI/ copper strips for grounding connections, using necessary fixing materials as required.25 x 3mm G.I strip.complete as per specifications and directions of the Engineer in charge.	Rm	75.08	Rupees Seventy Five And Paise Eight Only
132	32.00	Supplying and fixing of slim box Fitting ,made out of CRCA sheet metal body with locking type holder completely wired Excluding Ballast &Flouresent Tube. 1X4' Tube light Fitting.complete as per specifications and directions of the Engineer in charge.	Nos	303.19	Rupees Three Hundred Three And Paise Nineteen Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	2.00	Supplying capacitor type ceiling fan complete with down rod blades shackle, canopies etc, for operation on 230 volts, 50 cycles. single phase AC supply conforming to ISS-374-1979 and with double ball bearing system .complete as per specifications and directions of the Engineer in charge.48" sweep (1200mm)	Each	2112.69	Rupees Two Thousand One Hundred Twelve And Paise Sixty Nine Only
134	4.00	Supply Exhaust fan if 1440 RPM of (12") size with dracket blades complete for light duty suitable to -oerate on 230V 50Hz, supply complete as per specifications and directions of the Engineer in charge	Each	1212.75	Rupees One Thousand Two Hundred Twelve And Paise Seventy Five Only
135	1.00	Fabricating supplying and mounting MS box made out ...SWG suitable for floor I wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete . 14SWG	Sq.cms	25265.63	Rupees Twenty Five Thousand Two Hundred Sixty Five And Paise Sixty Three Only
136	2.00	Supplying .....amps rated 3phase with neutral bus bar using required capacity electrolytic aluminum strips covered with heat shrinkable coloured PVC sleeve, mounted on phenoliciFRP/DMC insulator which are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete. 1000Amps 4x75x10mm Alluminium Strips. complete as per specifications and directions of the Engineer in charge	Mtr	4884.69	Rupees Four Thousand Eight Hundred Eighty Four And Paise Sixty Nine Only
137	4.00	Supplying and fixing angle iron frame work iabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc.,and painted with 2 coats of red oxide and then two coats of approved paint. 75x75x6mm.complete as per specifications and directions of the Engineer in charge	Mtr	481.25	Rupees Four Hundred Eighty One And Paise Twenty Five Only
138	4.00	Supplying and fixing angle iron frame work iabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc.,and painted with 2 coats of red oxide and then two coats of approved paint. 75x150x50x6mm C channel.complete as per specifications and directions of the Engineer in charge	Mtr	654.50	Rupees Six Hundred Fifty Four And Paise Fifty Only
139	1.00	Supplying and Fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete, protection of Overload and Short circuit with thermal Magnetic/Microprocessed release and Earth Fault as per IS-13947.63/100Amps 25kA.complete as per specifications and directions of the Engineer in charge	Each	5871.25	Rupees Five Thousand Eight Hundred Seventy One And Paise Twenty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

		Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	10.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' cure, indicator ON/OFF, energy cross-3 with Short circuit breaking cappacity of 10K and complete wiring as required. Confirming to IEC 60898. 40-63Amps TPN.complete as per specifications and directions of the Engineer in charge	Each	1956.76	Rupees One Thousand Nine Hundred Fifty Six And Paise Seventy Six Only
	6.00	Qty Above 125%		1956.76	Rupees One Thousand Nine Hundred Fifty Six And Paise Seventy Six
141	1.00	Supplying and fixing Trivector meter suitable for operation LT operation and CT operated meter in polycarbonate body in class 0.5accuracy as per IS 14697 and completely wired.complete as per specifications and directions of the Engineer in charge	Each	3818.24	Rupees Three Thousand Eight Hundred Eighteen And Paise Twenty Four Only
142	1.00	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C. 50 Hz 12/24v D.C.complete as per specifications and directions of the Engineer in charge	Each	447.56	Rupees Four Hundred Forty Seven And Paise Fifty Six Only
143	1.00	Supplying, fixing and wiring 50/5 to 1000/5Amps 5VA burden Current Transformer. Class 0.5 accuracy with Tape Wound .complete as per specifications and directions of the Engineer in charge	Each	727.65	Rupees Seven Hundred Twenty Seven And Paise Sixty Five Only
144	0.00	Dismantling of barbed wire fencing / wire mesh fencing including posts, foundation concrete, back filling of pit by manual means including disposal of dismantled material with all lifts and stacking serviceable material and unserviceable material separately complete as per specifications. MORTH Specification No. 202.complete as per specifications and directions of the Engineer in charge	m	141.49	Rupees One Hundred Forty One And Paise Forty Nine Only
145	0.00	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. II. By Mechanical Means. A. Cement Concrete Grade M-15 &M-20. MORTH Specification No. 20.complete as per specifications and directions of the Engineer in charge	Cum	487.99	Rupees Four Hundred Eighty Seven And Paise Ninety Nine Only
146	0.00	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications and directions of the Engineer in charge.	Cum	399.44	Rupees Three Hundred Ninety Nine And Paise Forty Four Only
147	0.00	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications and directions of the Engineer in charge.	Cum	2601.64	Rupees Two Thousand Six Hundred One And Paise Sixty Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	0.00	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications and directions of the Engineer in charge.	Cum	5479.51	Rupees Five Thousand Four Hundred Seventy Nine And Paise Fifty One Only
149	0.00	Providing two line dressing to granite stone slab / granite stone masonry as per specifications and directions of the Engineer in charge.	Sqm	1601.60	Rupees One Thousand Six Hundred One And Paise Sixty Only
150	0.00	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications and directions of the Engineer in charge.	Cum	5808.69	Rupees Five Thousand Eight Hundred Eight And Paise Sixty Nine Only
151	0.00	Construction of embankment with approved material Gravel /Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. complete as per specifications and directions of the Engineer in charge.	Cum	348.43	Rupees Three Hundred Forty Eight And Paise Forty Three Only
152	0.00	Executive Bench- Made out of Sadarahalli grey stone with hand supports with 3 line finishing with arch design with 100mm slabs. Height 90x Length 1500 width 45 cms (Data approved rate)	Each	18393.38	Rupees Eighteen Thousand Three Hundred Ninety Three And Paise Thirty Eight
153	2.00	Supplying of dustbin for collection of dry and wet waste for segregation, (Fiber dustbin Modern Type 3.0-3.75 Ft) inclusive of all taxes and transportation charges as per the direction of Engineer in Charge (Data approved rate)	Each	18191.25	Rupees Eighteen Thousand One Hundred Ninety One And Paise Twenty Five
154	0.00	Providing and laying of Filter media with granular materials /stone crushed aggregates satisfying the requirements laid down in clause 2504.2.2. of MORTH specifications to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical Specification including cost of materials, labour, HOM complete as per specifications and directions of the Engineer in charge.	Cum	2239.74	Rupees Two Thousand Two Hundred Thirty Nine And Paise Seventy Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

		Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	0.00	Providing and constucting pithcing / Revetment of 30 cm thick on slopes using granite/basalt/trap/stones of surface area not less than 0.04 sqm and wedged with spalls including cost of all materials, labour, HOM etc., complete as per specification and directions of the Engineer in charge.	Sqm	470.72	Rupees Four Hundred Seventy And Paise Seventy Two Only
EIRL-1	622.22	KSRB15-3:Providing 20mm thick cement plaster in single coat with cement mortar, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering ,including providing and removing scaffolding ,cost of materials ,labour,curing etc complete as per specificatio.KSRB15-3.12 do-cement mortar 1:6	Sqm	277.06	Rupees Two Hundred Seventy Seven And Paise Six Only
EIRL-2	751.70	Earthwork excavation in all soil deposits and filling sides of foundatiaon upto plinth in layers not exceeding 20cms ,in depth compacting each deposits layer by ramming after watering with all lead and lift including cost of all labour complete as per specification	cum	439.59	Rupees Four Hundred Thirty Nine And Paise Fifty Nine Only
EIRL-3	1920.00	Fabricating, providing and erecting in poiston of M.S. Ornamental security Grill Gate without hot dip using 75 x 12mm M S Flat for alround frame work with verticals at.the centre and horizontal centere support M S Square of 20 x20 mm of different heights as shown in the drawing are to be fixed at 16 cms C/C for square bars of full height and at 8cms C / C for bottom rods providing ornamental C I Designers at the bottom and CI arrows in the midle and top. The entire frame work is to be fixed by means of expansion bolts to the brick pillars with necesary drilling holes, the work includes providing two coats of enamel painting over one coatr of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes with all lead and lift, loading, transporting and unloading using hoist pulley cranes, scaffolding charges and all other incidental charges required for successful completion fo the work as per specification and drawings	Kg	142.56	Rupees One Hundred Forty Two And Paise Fifty Six Only
EIRL-4	287.19	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406		2059.43	Rupees Two Thousand Fifty Nine And Paise Forty Three Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

		Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
EIRL-5	29.88	KSRB 7.14 : Providing, fabricating, assembling and fixing in position aluminium partitions using sections in combination of plain, single grove and double grove as per requirements for the frames of overall size 101.6mm x 44.45mm, 3.18mm.thick having section weight, plain sections 2.40kg/m single grove section 2.541kg/m. and double grovesection 2.683 kg/m and bottom 46 kg/m; aluminium louvres of size 77.6mmx27.6mm 1.7mm. thick section weight 0.483kg/m; bottom portions provided with 12mm. thick prelaminated sheet both side of approved colour lamination exterior grade; aluminium sections of mat finish or glossy finish using section, spacing of vertical member shall not exceed 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames, the assembled frame should be stiffened with corner angles stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns or masonry on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistling and making good with cement mortar to match the surface, providing and fixing bottom panel filled with the materials to a height of 0.9m. from floor level; and		5142.03	Rupees Five Thousand One Hundred Forty Two And Paise Three Only
EIRL-6	11.15	KSRB 7.17 : Providing, fabricating, assembling and fixing in positionaluminium doors using following aluminium mat finish or glossy finish, outer frame plain section 101.6x44.45mm thickness 3.18mm,section weight 2.404 kg/m, door shutters vertical section 44.62x44.45mmthickness 3.18mm, section weight 1.505kg/m, top section 47.62x44.45mm thickness 3.00mm, section weight 1.426kg/m bottom section 114.3x44.45 thickness 3.18mm, section weight 2.646kg/m, door central section49.91x44.45mm thickness 3.00mm, section weight 1.495 kg/m glazingclips 19x17.3x11mm thickness 0.9mm section weight 0.124kg/m;aluminium sections cut to length joint metred corners grinded, theshutters pivoted opening arrangement with heavy duty aluminium alloy automatic door closures floor mounted, providing and fixing standard approved accessories, such as aluminium handle for full width or length, tower bolts, lock, pivots: P.V.C. or rubber gasket with 5.5m. thick plain glass for top and bottom panel; aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherance of mortars or any other sticky materials; the assembled frame fitted with the corner	Sqm	6784.78	Rupees Six Thousand Seven Hundred Eighty Four And Paise Seventy Eight Only
EIRL-8	8.00	Providing and fixing Turbo Exhuast fan at the height of 11m making holes for fixing in roof sheets including all fixtures and labour charges and ceilen	No	12000.00	Rupees Twelve Thousand Only
EIRL-9	55.00	Providing and Fixing LED LIGHTS Of length 0.9m including nets and bolts fixed over Exsiting pipe inclusive of labour charges etc	NO	7000.00	Rupees Seven Thousand Only
EIRL-10	4.00	Supplying and fixing Net pole total weight 200KG Material used :Carborudum poles guage 14gauge ,Top wheel type metal,Paint type EpoxyPainting Movable type Portable on wheels Height 5.1Ft Tappered box with Yonex Standard Net as per specification etc complete includiing transporation installation at site	No	32000.00	Rupees Thirty Two Thousand Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Scanned by TapScanner

		Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
		Providing and fixing windows blinds including top aluminium chanel with bearing 4inches fabric stripes with handling rod gear and total operating systems .The price inclusive of GST Transportion and installation complete as per the Direction in charge		1530.15	Rupees One Thousand Five Hundred Thirty And Paise Fifteen Only
EIRL-12	3.36	Providing and fixing Stainless steel 304 grade for staircase railings, balconies, ramps with hand rail, 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications	Sqm	6567.71	Rupees Six Thousand Five Hundred Sixty Seven And Paise Seventy One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore

Scanned by TapScanner